

Risk has been calculated by using the following Severity, Likelihood and Risk Rating tables

Table 1: Severity (S)

Description	Code	Definition
Major	3	Single or multiple fatality / severe Injury -Fracture of major bone or skull, loss of limb or eye, permanent loss of sight or hearing, acute illness requiring medical treatment, unconsciousness where person has to be resuscitated, any injury leading to more than a month off work.
Moderate	2	Fractures to hands, wrist ankles etc., leading to between 7 days and a month off work
Minor	1	Minor Injury Fracture of digits (fingers, toes), strains and sprains, scratches, cuts, abrasions, bruising, minor burn, general discomfort, minor ill health, allergies, minor temporary illness (e.g. eye strain, back strain), any injury leading to less than 7 days off work

Table 2: Likelihood (L)

Description	Code	Definition
High	3	Frequent / Every week
Medium	2	Likely / Every month
Low	1	Infrequent / Every year

	High (3)	Medium Risk (4) High Risk (5)		High Risk (6)				
po	Medium (2)	Low Risk (3)	Medium Risk (4)	High Risk (5)				
Liklelihood	Low (1)	Low Risk (2)	Low Risk (2)	Medium Risk (4)				
Lik	Risk matrix	Minor (1)	Moderate (2)	Major (3)				
	Severity							

Table 3: Risk Rating Matrix (R)

Add Likelihood ande&erity numbertsogether to give Risk Rating

= 3 or less risk is Low	= 4 risk is Medium	= 5 or more risk is High



Risk Assessment

CLIENT	Bridge Expo						
PROJECT	Stand Build						
DATE	26 and 27 Nov 25						
SUMMARYOFRISKTOBEASSESSED	Specifically, the delivery, erection, adaptation and dismantling of scaffolding.						
	Standards	All structures to be erected in accordance with Layher Ltd.'s Safe systems of work, policies and procedures, the Client's requirements and in compliance with relevant NASC and industry guidelines including BS EN 12811-1 All materials to comply with relevant standards BS EN 12810 BS2482, BS EN 74, BS EN 39 and can be traced to origin of manufacture. All materials supplied by quality assured companies.					
	Risk Assessment	Prior to any works, Layher Ltd will assess all risks connected with the project.					
	Method Statement	Prior to any works, a safe method of working will be agreed with the Client.					
	Handover Certificate	When the scaffold structure is complete and ready for use, Layher Ltd will issue a Handover Certificate to the Client.					
	COSHH Regulations	All scaffolding products used in the construction and for servicing equipment, comply with the Control of Substances Hazardous to Health Regulations.					
	Scafftag Safety Management System	N/A					
	Inspection Report Work at Height Regs 2005 & CDM Regs 2015	Under Regulation 12 of the Work at Height Regulations 2005, every scaffold must be inspected before first use, every 7 days, after any event likely to have affected its strength or stability, and after any substantial addition, dismantling or other alteration. In order to comply with Regulation 12(7), particulars of each inspection must be recorded in a Report of Inspection. Under Regulation 3, it is the responsibility of every employer to ensure that the requirements of the Regulation which apply to their own employees are complied with.					



Risk Assessment

Ref	Description of Hazard	escription of Hazard Risk to Risk Control Measures		Post Control Residual Risk Estimate			Risk Owner
				S	L	Risk	
1.	Delivery of scaffolding material Risk of a range of injuries from major (vehicle movements) to minor (grazes to hands)	The Public Other Trades Scaffolders	Divert or organise pedestrians and/or traffic Organise deliveries with the Client Follow designated Traffic plan, arrange delivery area Arrange temporary barriers Fix lighting and warning notices as necessary. Appropriate PPE (e.g. Hi-Viz, hard hat, boots, gloves) to be used at all times Banksmen to guide Layher Ltd vehicle when reversing	2	1	LOW	Client and Layher Ltd
2.	Materialshandling Risk of a range of injuries from minor (back strain) to fatality	Scaffolders Other Trades The Public	Driver checks loads secure before driving on public roads Cordon off handling area SG6 Training in and use of recommended lifting techniques Use mechanical lifting equipment, gin wheels, hoists or craneage where appropriate.	1	1	LOW	Client and Layher Ltd Employees have duty of care
3.	Scaffold Materials Minor to major injuries as a consequence of defective materials	The User Scaffolders Other Trades The Public	Service and maintain regularly Inspect all materials before loading Inspect all materials again before use Quarantine any defective materials and return to depot for scrapping or repair	1	1	LOW	Layher Ltd
4.	Cutting of tube and boardsiten Minor to severe injuries through incorrect use of cutting equipment	NA		1	1	LOW	Layher Ltd



Risk Assessment

Post Control Ref Description of Hazard Risk to Risk Control Measures Residual Risk Risk Owner Estimate S Risk Erecting scaffolds 2 1 Scaffolders All scaffolding erected, adapted and dismantled only by our trained Layher Ltd Major injuries through falls of operatives persons as a result of incorrectly Scaffolders to be H&S Tested and registered on CITB CISRS Construction constructed structures; inadequate Industry Scaffolders' Record Scheme edge or opening protection and The wearing of safety harness to be in strict accordance with NASC Guidance access (unsafe ladders); poor Note SG4 housekeeping standards creating Carry out pre-start risk assessment for someone suspended in safety harness risks of tripping and include within the Method Statement Work area to be cordoned off and signs to warn scaffold erection in progress as necessary All materials to be raised or lowered using recommended lifting procedures Partially erected scaffolds The User Always complete scaffold section being erected 1 LOW Layher Ltd Major injuries through falls of The Public Cordon off scaffold to prevent unauthorised access and/or Client Secure ladders to prevent unauthorised access persons as a result of premature Scaffolders and unauthorised use of scaffold Fix Scaffold Incomplete warning signs Adaptions/Additions/and Scaffolders As for 5 above (Erecting scaffolds) plus: 2 1 LOW Lavher Ltd Dismantling of scaffold The User Correct stacking and control of existing scaffold materials. and Client Major injuries through falls of The Public Reverse order of erection process to dismantle persons as a result of incorrectly constructed structures; inadequate We would emphasise: edge or opening protection and All scaffolding adapted only by our trained operatives access (unsafe ladders); poor housekeeping standards creating risks of tripping. Injuries also resulting from unauthorised adaption of scaffold

Page 4 of 8



Risk Assessment

Page 5 of 8

Ref	Description of Hazard	Risk to	Risk Control Measures		Resid	Control ual Risk imate	Risk Owner
				S	L	Risk	
8.	Completed scaffolds Major injuries through falls of persons as a result of incorrectly constructed structures; inadequate edge or opening protection and access (unsafe ladders); poor housekeeping standards creating risks of tripping	Other Trades The Public	All scaffolding erected, adapted and dismantled only by our trained operatives Safe means of access and egress to be provided Edge protection to be provided After Handover: Trades using the work platforms have a duty of care to check there have been no unauthorised alterations carried out after our handing over, for example: (a) Ensure no handrails have been removed (b) Ensure toeboards are still in place (c) Ensure all brickguards are still in place (d) Ensure that boards have not been removed from the working platform (e) Ensure that ladders are correctly tied, the correct length and angle	2	1	LOW	Pre Handover: Layher Ltd Post Handover: the Client
9.	Unauthorised scaffold alteration by others	The Public The User	Competent person in charge of labour using the scaffold to carry out daily inspection prior to use. CSL to carry out statutory weekly inspection, as per client request. Scaffolders to make visual check before starting work; Check structure/bracing/ties/base; and check boarded lifts are safe to use. Any interference to be reported to Layher Ltd office.	1	1	LOW	Client's Site Manager and Layher Ltd
10.	. Working area not cordoned off Client Major to minor injuries	The Public Other Trades Scaffolders	No scaffolding works to proceed Layher Ltd office to be contacted for instruction Protection fans/covered walkways to be installed before any work is carried out to the main structure.	2	1	LOW	Client



${\color{blue} \textbf{More possibilities}.} \textbf{The Scaffolding System}.$

Risk Assessment

SSESSMENT Page 6 of 8

Ref	Description of Hazard	cription of Hazard Risk to Risk Control Measures		Post Control Residual Risk Estimate			Risk Owner
				S	L	Risk	
11	Falling materials/tools Head and other injuries through falling materials; damage to property.	Scaffolders Other Trades The Public	"No Go" areas are to be designated under and around the work areas while erection/dismantling is in process. Warning signs to be displayed. Ensure handrails, toeboards are in place on all working platforms / loading bays at all times. Swing-over gates used to facilitate loading by forklift. Brickguards/debris netting/Monarflex to be installed where scaffold is required for stacking materials. Scaffolding materials to be neatly stacked and secured when not being used. Correct procedure used with bags/buckets for fittings. Raising and lowering of materials by controlled means only. CSL operatives to use Tool Tethers/Lanyards.	2	1	LOW	Client for "No Go" areas Layher Ltd
12	Waste materials Slips/Trips due to waste materials being left lying around	Scaffolders Other Trades The Public	All waste materials to be cleared from site and returned to yard for recycling/safe disposal Work area to be swept & debris cleared	1	1	LOW	Layher Ltd Client
13.	Unusual ground conditions / foundation for the scaffolding Injury through collapsing scaffolding following ground movement or subsidence	Scaffolders Other Trades The User The Public	Information gathering at site survey or at Pre-Contract/Start Meetings and/or from the Health and Safety Plan. Client to advise on ground conditions prior to erection of scaffold. Timber spreaders to be used on soft ground.	2	1	LOW	Client
14	Unsafe structures Fall or crush injuries caused by collapse of building, walls, roof and fragile surfaces e.g. roof lights.	Scaffolders Other Trades The User The Public	Information gathering at site survey or at Pre-Contract/Start Meetings and/or from the Health and Safety Plan. Client / structural engineer to advise of any fragile, non load-bearing surfaces prior to erection of scaffold. Scaffold to be designed to accommodate. Tie points for scaffold to be indicated on job sheet/method statement. Create safe work area, board over or handrail off roof lights.	2	1	LOW	Jointly Client Scaffold Designer and Layher Ltd



Risk Assessment

Ref	Description of Hazard Risk to Risk Control Measures		Risk Control Measures	Post Cont Residual R Estimate			Risk Owner
				S	L	Risk	
15.	Public rights of way, nearby ro schoolstc. Injuries to the general public, especially children, resulting from inadequately guarded operations	The Public	All local authority permits to be applied for in advance Warning notices to be clearly displayed; working area to be cordoned off; delivery, erection and dismantling to be planned to avoid busy periods; all materials to be secured; unauthorised access to be prevented, e.g. by boarding ladders during breaks and removing ground level ladders at the end of each working day; lights and Hi-Viz markings to be in accordance with LA regs; protection fans / pavement gantries to be installed as appropriate.	2	1	LOW	Pre scaffolding works – Client During works – Layher Ltd After Handover – Client
16.	TraineeScaffolders Inexperienced Scaffolders injuring themselves or others	Scaffolders Other operatives	All trainees to be supervised at all times by qualified Scaffolder Safety training and induction to be given to all new personnel. All new Trainees to be given minimum one full day H+S Training CISRS COTS	1	1	LOW	Layher Ltd
17.	Mechanical/electrical/other equipment Injuries through incorrect use of mechanical handling equipment during the transportation of scaffolding materials around the site; injuries through incorrect use of saws, drills, grinders etc.	Scaffolders	N/A	1	1	LOW	Client Layher Ltd
18.		The Public The User Other Trades Scaffolders	No work to proceed during adverse weather conditions Scaffold to be designed to relevant wind code. Boards to be strapped down on exposed scaffolds to prevent displacement in high winds Adequate ties to be fixed to exposed sheeted scaffolds No signs or hoardings to be fixed to the scaffolding without prior consultation with Layher Ltd Reference HSE Guidance HSG33 Health and Safety in Roof Work , work at height to cease where the mean wind speed reaches 23 mph (gusting to 35 mph or over)	1	1	LOW	Prior to Handover Layher Ltd After Handover the Client

Page 7 of 8



Risk Assessment

Page 8 of 8

MAINTENANCE AND NSPECTION

- A Handover Certificate will be issued by Layher Ltd on completion of section of scaffold. Site Manager to ensure scaffolds are properly constructed before accepting handover and taking into use, a signed receipt is required by Layher Ltd.
- 2. The inspection by the Site Manager or a competent person on behalf of the Client to be recorded in the WAHR 2005 Inspection Report. This record to be available for inspection on site.
- 3. All scaffolds to be inspected by the Site Manager after substantial addition or alteration and after any event likely to have affected its strength or stability, and at regular intervals not exceeding seven days
- 4. The Site Manager should carry out basic daily checks at the beginning of each day before allowing other trades to work on the platforms.